



Tyler Boldt
tboldt@garlandcanada.com

QUICK QUOTE

Garland Canada Inc. ©
209 Carrier Drive
Toronto, Ontario M9W 5Y8
www.garlandcanada.com

Client:	Salthill Capital
Job:	Roof Replacement - Royal Oak Park - 1.6.1

September 24, 2025

Notes

Section 1.6.1

1. Remove and dispose of existing simulated grass and underlying gravel.
2. Remove existing rubber matting and set aside for re-use.
3. Remove existing insulation and set aside for re-use.
4. Remove and dispose of existing TPO membrane.
5. Inspect existing gypsum board and repair as necessary.
6. Install new 0.5" DensDeck Prime, adhered Insul-Lock HR adhesive, joints staggered with layer beneath.
7. Fire tape seams of DensDeck Prime.
8. Torch-apply new Garland HPR Torch Base.
9. Torch-apply new Garland StressPly IV Plus cap sheet.
10. Picture frame all perimeters and projections using Garland SA Base IV.
11. For picture framing, prime with Pro-Stop FR Primer.
12. Reinforce all vertical seams with Garla-Flex and GarMesh.
13. Once base and cap sheet is installed, perform a flood test with a Garland representative present.

FOB Toronto plus any Fuel Surcharges

Terms: 1 1/2% DISCOUNT 10 DAYS - A FINANCE CHARGE OF 2% PER MONTH WILL BE ADDED TO THE UNPAID BALANCE 45 DAYS AFTER INVOICE DATE. TARIFFS EXTRA TO QUOTED PRICES.

*Printed 09/24/2025 - **Quote is valid 30 days from this date.***

© 2025 Garland Industries, Inc.



Tyler Boldt

tboldt@garlandcanada.com

QUICK QUOTE

Garland Canada Inc. ©

209 Carrier Drive

Toronto, Ontario M9W 5Y8

www.garlandcanada.com

14. Install new drainage mat.

15. Re-install insulation.

16. Install new metal flashings.

Please refer to the cut test photo report in project files for existing roof system composition.

Roofing contractor to carry \$15,000 for removal and reinstallation of metal wall panels.

Roofing contractor to engage with and carry cost for glazing professional to assist in removing and reinstalling metal flashings along walls with windows.

FOB Toronto plus any Fuel Surcharges

Terms: 1 1/2% DISCOUNT 10 DAYS - A FINANCE CHARGE OF 2% PER MONTH WILL BE ADDED TO THE UNPAID BALANCE 45 DAYS AFTER INVOICE DATE. TARIFFS EXTRA TO QUOTED PRICES.

*Printed 09/24/2025 - **Quote is valid 30 days from this date.***

© 2025 Garland Industries, Inc.



Tyler Boldt
tboldt@garlandcanada.com

QUICK QUOTE

Garland Canada Inc. ©
209 Carrier Drive
Toronto, Ontario M9W 5Y8
www.garlandcanada.com

Product #	Description	Coverage Rate	Unit Price	Quantity	Total Price
4383	StressPly IV Plus Poly/Fiberglass-reinforced SBS modified bitumen membrane (torch)	75 sq. ft./roll (26'2" x 3'3") (Pkg: ROLL)	\$599.00 (RL)	1	\$599.00
4113	HPR Torch Base Fiberglass-reinforced SBS-modified bitumen base sheet for torch-applied membranes	100 sq. ft./roll (34' 8" x 3'3") (Pkg: ROLL)	\$538.00 (RL)	1	\$538.00
4150	SA Base IV Fiberglass-reinforced SBS-mod. self-adhering base ply for torch-applied membranes	100 sq. ft./roll (34'8" x 3'3") (Pkg: ROLL)	\$515.00 (RL)	1	\$515.00

FOB Toronto plus any Fuel Surcharges

Terms: 1 1/2% DISCOUNT 10 DAYS - A FINANCE CHARGE OF 2% PER MONTH WILL BE ADDED TO THE UNPAID BALANCE 45 DAYS AFTER INVOICE DATE. TARIFFS EXTRA TO QUOTED PRICES.

Printed 09/24/2025 - **Quote is valid 30 days from this date.**

© 2025 Garland Industries, Inc.



Tyler Boldt
tboldt@garlandcanada.com

QUICK QUOTE

Garland Canada Inc. ©
209 Carrier Drive
Toronto, Ontario M9W 5Y8
www.garlandcanada.com

Product #	Description	Coverage Rate	Unit Price	Quantity	Total Price
7640-19	Pro-Stop FR Primer New water based intumescent coating for wood components Garland roof assemblies	0.5 gal./sq. 200 sq. ft./gal. (Pkg: 19 LITER PAIL)	\$939.00 (PL)	1	\$939.00
2143	Seal-Tite Single Part STPE Pitch Pocket Box (4 2L bags per box)	2 2LBags fill 3 6"X6"X2" pitch pans (Pkg: BOX)	\$508.00 (KT)	1	\$508.00
9332-20	Garla-Flex High quality flexible elastomeric asphaltic mastic used w/ GarMesh	5-6 sq. ft./gal. (Pkg: 19 LITER PAIL)	\$542.00 (PL)	1	\$542.00
4840-6	GarMesh 6" SBS coated woven fiberglass reinforcing fabric	75 sq. ft./roll (150' x 6") (Pkg: ROLL)	\$105.00 (RL)	1	\$105.00
7347	Insul-Lock HR High rise urethane insulation adh for new construction or gravel recovers (4 cart./case)	150 sq.ft./cart. @ 12" o.c. (Pkg: CASE OF 4)	\$880.00 (CS)	1	\$880.00

Total Material: \$4,626.00

Total Price: \$4,626.00

FOB Toronto plus any Fuel Surcharges

Terms: 1 1/2% DISCOUNT 10 DAYS - A FINANCE CHARGE OF 2% PER MONTH WILL BE ADDED TO THE UNPAID BALANCE 45 DAYS AFTER INVOICE DATE. TARIFFS EXTRA TO QUOTED PRICES.

Printed 09/24/2025 - **Quote is valid 30 days from this date.**

© 2025 Garland Industries, Inc.